



ADDENDUM NO. 1
TO
CONTRACT DOCUMENTS
FOR
WATER MAIN REPLACEMENT AT VARIOUS LOCATIONS
IN
ANTIOCH, CALIFORNIA
P.W. 503-18

ISSUED
DECEMBER 11, 2019

This Addendum No. 1 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

SEE ATTACHED ADDENDUM ITEMS

Prepared By: 
Scott Buenting, P.E.



BIDDER'S CERTIFICATION

I acknowledge receipt of this Addendum No. 1 and accept all conditions contained herein.

Bidder

By:

ADDENDUM NO. 1

Water Main Replacement at Various Locations P.W. 503-18

Issued December 11, 2019

- 1) The sixth paragraph of Section C-4, "Obstructions", is amended to state the following:

"The Contractor shall be responsible for the replacement of any and all facilities, including but not limited to, all landscaping, irrigation facilities, traffic loops, asphalt concrete and concrete flatwork, removed or damaged during the duration of the project. Existing concrete curb, gutter, sidewalk, and driveways shall be removed as necessary at construction joints, and replaced to the lines, grades, and dimensions of the existing improvements and per City of Antioch Construction Details ST-02a, ST-02b, ST-02c, ST-02d, ST-03ST-04, ST-05, ST-06 or ST-07 and as directed by the Engineer. All new concrete shall be connected to existing concrete with dowels. New concrete curb shall have eighteen inch (18") long No. 4 bar dowels embedded nine inches (9") into each end of the existing concrete curb. Concrete sidewalk and driveway have eighteen inch (18") long No. 4 bar dowels, installed eighteen inches (18") on center, embedded nine inches (9") into the adjacent existing concrete sidewalk or driveway and twelve inch (12") long No. 4 bar, installed eighteen inches (18") on center embedded three inches (3") into the back of the existing concrete curb. The cost of replacing existing facilities shall be borne completely by the Contractor. If existing facilities are to be replaced or relocated, they shall be done so in accordance with the applicable City Standards and as directed by the Engineer."

- 2) Section C-12, "Copper Water Services", is amended to include the following:

"Excavation, directional drilling and pneumatic moling are all acceptable methods of installing water service laterals."