



ADDENDUM NO. 1

TO
SPECIFICATIONS
FOR
COUNTRY HILLS DRIVE
SANITARY SEWER MAIN REHABILITATION
IN
ANTIOCH, CALIFORNIA
P.W. 545-1

ISSUED
June 30, 2014

This Addendum No. 1 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

SEE ATTACHED ADDENDUM ITEMS

Prepared By: _____

Scott Buenting, P.E.



BIDDER'S CERTIFICATION

I acknowledge receipt of this Addendum No. 1 and accept all conditions contained herein.

Bidder

By:

- 1) The first paragraph of the "Notice Inviting Bids" is amended to state the following:

"NOTICE IS HEREBY GIVEN THAT sealed bids will be received by the Office of the City Clerk of the City of Antioch at Antioch City Hall, located at 200 "H" Street Antioch, California 94509, until 2:00 p.m., July 8, 2014, at which time bids will be publicly opened and read in the City Council Chambers located at 200 "H" Street, Antioch, California 94509".

- 2) The third paragraph of the "Notice Inviting Bids" is amended to state the following:

"Bids shall be submitted on the City's Bid Forms included in the Contract Documents, plainly endorsed with Bidder's name together with signed acknowledgment of any and all addenda. Bid Forms shall be securely sealed in a suitable envelope marked with the name and address of the Bidder, and marked in capital letters on the front and back of the envelope, as follows:

**Country Hills Drive
Sanitary Sewer Main Rehabilitation
P.W. 545-1
July 8, 2014
(Name and Address of Bidder)"**

- 3) The first paragraph of Division A, Section A-1, Bid Opening and Award, is amended to state the following:

"Sealed proposals will be received by the Office of the City Clerk, City Hall, located at 200 "H" Street, Antioch, California, until 2:00 p.m., July 8, 2014, publicly opened and read in the City Council Chambers located at 200 "H" Street at 2:00 p.m., July 8, 2014."

- 4) The attached "Schedule of Bid Prices", dated July 8, 2014 shall be submitted in lieu of the original "Schedule of Bid Prices", dated July 1, 2014.

- 5) Item 'C' of Section 01025, "Measurements and Payment", Subsection 4.0 "Description of Bid Items", is amended to state the following:

"BID ITEM 2: Rehabilitation of 12-inch Diameter Sanitary Sewer by CIPP Method - Bid Item 2 includes payment for all labor, materials, tools, equipment, testing and incidentals necessary for sanitary sewer rehabilitation using trenchless cured-in-place pipe (CIPP) method. Measurement and payment shall be made at the contract unit price bid per horizontal "Lineal Foot" from the center of the upstream and downstream manholes and shall be full compensation for design calculations, submittals, post installation cleaning, pre and post installation television inspection, furnishing and proper installation of the liner, reinstating service laterals, sealing liner at connections to manholes, verification of pipe length and diameter, grade, bends, curves, liner sampling and testing, cure water discharge sampling, testing, and treatment, all manhole restoration required to accommodate liner installation, all permits, and all other work required for proper rehabilitation of the pipelines."

- 6) Item 'A' of Section 02060, "Cleaning of Sanitary Sewer Mains", Subsection 1.01, "Description of Work", is deleted from the Special Provisions.

- 7) Item 'A' of Section 02060, "Cleaning of Sanitary Sewer Mains", Subsection 3.01, "Pipeline Cleaning Setup", is deleted from the Special Provisions.

- 8) Item 'B' of Section 02070, "Television Inspection of Sanitary Sewer Mains", Subsection 1.01, "Summary", is amended to state the following:

"Prior to each television inspection, all sewage flow shall be adequately controlled within the pipeline sections to be cleaned and inspected, and the sewer shall be thoroughly cleaned as required by these specifications."

- 9) Section 02070, "Television Inspection of Sanitary Sewer Mains", Subsection 3.01, "Cleaning of Existing Host Pipe", is amended to state the following:

"Prior to conducting closed circuit television inspection it shall be the responsibility of the Contractor to thoroughly clean the host pipe, per Section 02060."

- 10) Item 'C' of Section 02070, "Television Inspection of Sanitary Sewer Mains", Subsection 3.02, "TV Inspection and Pre- and Post- Rehabilitation Sewers", is amended to state the following:

"Video inspection shall be performed in the presence of the Engineer on one sewer segment at a time. The Contractor shall be responsible for cleanup, repair and property damage costs and claims should the Contractor's operation cause any backups or overflows. The Contractor shall also reimburse the City the full cost of any and all fines the City is required to pay as a result of a backup or overflow. Should the camera get stuck in the sewer, the Contractor shall be responsible for all costs in extracting it. Costs related to difficulties encountered during internal video inspection are incidental to the contract, and claims will not be considered."

- 11) Item 'B' of Section 02145, "Sewer Flow Control", Subsection 1.01, "Summary", is deleted from the Special Provisions.

- 12) Item B-1-e of Section 02145, "Sewer Flow Control", Subsection 1.02, "Submittals", is amended to state the following:

"Provide calculations proving adequacies of the bypassing system and selected equipment."

- 13) Item B-1-h of Section 02145, "Sewer Flow Control" Subsection 1.02, "Submittals", is amended to state the following:

"Identify and designate a responsible person for Contractor that shall be responsible for monitoring and have the ability to correct problems with the bypass/diversion system(s)."

- 14) Item 'B' of Section 02145, "Sewer Flow Control", Subsection 2.01, "Primary Flow Control Pumps and Generators", is amended to state the following:

"A minimum of one primary pump and one standby pump is required for each flow control system. The standby pump shall be at least the same capacity as the primary pump."

- 15) Item 'A' of Section 02145, "Sewer Flow Control", Subsection 2.02, "Sewage Flow Control Piping", is amended to state the following:

"A minimum of one discharge pipe is required."

- 16) Item 'B' of Section 02145, "Sewer Flow Control", Subsection 2.02, "Sewage Flow Control Piping", is amended to state the following:

"The sewage flow control discharge shall consist of piping or lay-flat hose that is completely leak free. Any drips or leaks shall be repaired by the Contractor immediately."

- 17) Item 'D' of Section 02145, "Sewer Flow Control", Subsection 2.02, "Sewage Flow Control Piping", is deleted from the Special Provisions.

- 18) Item 'C' of Section 02145, "Sewer Flow Control", Subsection 2.03, "Temporary Bulkheads and Plugs", is deleted from the Special Provisions.