



**ADDENDUM NO. 1**  
**TO**  
**SPECIFICATIONS**  
**FOR**  
**PREWETT FAMILY WATER PARK FILTER REPLACEMENT AND**  
**RESURFACING**  
**IN**  
**ANTIOCH, CALIFORNIA**  
**P.W. 567-5**

**ISSUED**  
**February 4, 2013**

This Addendum No. 1 must be signed by the bidder and attached to the CONTRACT PROPOSAL PACKAGE for consideration by the City. The City reserves the right to disregard any proposal, which does not include this Addendum. The City may waive this requirement at its sole discretion.

**SEE ATTACHED ADDENDUM ITEMS**

PREPARED BY: \_\_\_\_\_

*Justin Pitcher*  
Justin Pitcher, City of Antioch

**BIDDER'S CERTIFICATION**

I acknowledge receipt of this Addendum No. 1 and accept all conditions contained herein.

\_\_\_\_\_  
Bidder

\_\_\_\_\_  
By:

The Following Technical specifications contradict the plan sheets. Clarifications are provided for each.

Section 13-80-00 - Pool Plumbing and Filter Room Equipment	The Specifications call for VFD's and associated equipment for 4 bodies of water and the plans say these units are existing. They are not existing and should be furnished and installed where shown on the plans.
Section 13-80-00 - Pool Plumbing and Filter Room Equipment	The specifications and plans differ on the item number for the replacement pool boilers. The correct model is <i>Raypak Digital Low NOX ASME cupro Nickle Natural Gas Heater B-R408A-EN-X #26</i> (2 locations).
Section 13-80-00 - Pool Plumbing and Filter Room Equipment	The Model number for the Lap Pool VFD should be updated to EF-C-46-12-2 Nema 12

**The Following Request for Information (RFI's) was received. Answers are provided below.**

How Many Pool Lights are to be replaced?	Please reference section 13-11-46 of the technical specifications. Lights, as required by pool, are listed here. This section also lists the types of lights required.
Is the Waterproofing sealant listed in the scope of the work for the expansion joints in the pool?	The Waterproofing sealant is specified for use between the existing deck and existing cast in place copping, as well as between the existing slides and the cement they are set into. This work includes the removal of existing sealant, prepping of joints and resealing of joints. Reference section 07-90-00 of the technical specifications for installation requirements.
Can you provide details for the VGB work?	Please reference section 13-90-00 of the technical specifications. The work for each pool is spelled out in that section.
When will the as-built drawings be made available?	Original pool drawings have been made available both in the plan room and by email to all bid-walk attendees.
Can you explain the Irrevocable Standby Letter of Credit Form?	The Irrevocable Standby Letter of Credit is used in lieu of the bond.

**The Following shall be added to SECTION B-8: Progression and Progress.**

J. Work on the Lap pool shall be scheduled with the City Engineer to limit the down time necessary for such work. This work shall be scheduled as early as possible, so that the City can provide notice to patrons that programs will be cancelled while work is taking place. The timeline for this work should be as limited as possible, as the City will have to cancel programs while the work is completed.