



Roof Replacements at Antioch Water Park and
Water Treatment Plant
Bid No. 770-1130-22A

ADDENDUM NO. 1
Dated November 17, 2022

Changes to Specifications

1. On Page 7 of 18 **replace** guideline 2. Through 6. with the following:
Antioch Water Treatment Plant concrete Deck Coating – 401 Putman St
(Building #10 on map)
 1. Beat blast entire surface.
 2. Prime roof surface with GarlaBlock 2k.
 3. Reinforce all seams with polyester reinforced butyl tape.
 4. Install Base Coat of Liquitec at 2.5G per 100sqft.
 5. Install Top Coat of Liquitec at 2.5G per 100sqft.
2. On Page 8 of 18 **replace** Antioch Water Park Map with Addendum No. 1 Map attached herein as Exhibit No. 1.

Additions to Specifications:

1. Insert the following section on Page 8 of 18 below **Antioch Water Park – 4701 Lone Tree Way,**
guideline 15. Flashings, details, clean up, etc.:
Antioch Water Park Siding
 1. Cut existing wood siding a minimum of 2ft vertically to remove all existing dry rot – 765sq ft
 2. Install new 2 ply modified base flashings at roof to wall.
 3. Install new 2 piece reglet at roof to wall termination.

This addendum must be included with your bid:

Company Name _____
Date Received _____
Signature _____
Name _____
Title _____